



City of Cottonwood
Fabrication and Erection of One (1) Powder Coated
Bolted Steel Reclaimed Water Storage Tank
2016-PW-10 Addendum #5
May 19th, 2016

Addendum 5 addresses additional questions which were asked regarding the tank. This is the final addendum which will be issued for this solicitation.

Questions: Is the 18" gradeband supposed to be painted, black or hot dipped galvanized? Next, are you requesting that the contractor remove 6" of existing compacted fill in order to fill the newly created void with 3/4" gravel or will the contractor be responsible for regrading the site and burying 6" worth of the gradeband with additional fill placed on top of the existing grade?

Please confirm you are requesting the floor of the referenced bolted tank to be fabricated out of 1/4" plate.

Answers: The 18" grade band shall be either painted or hot dipped galvanized.

Existing fill at the proposed site is graded to 3297.6 +/- and the finish floor elevation of the tank shall be 3298.50 as indicated on the plans. The contractor shall be responsible for excavating, installing and compacting around the grade ring so that it is embedded 6-inches as shown on the plans. Additionally, the contractor shall be responsible for removal of existing material within the footprint of the grade ring to accommodate the placement of the 1-foot of 3/4" clean ABC indicated on the plans.

The floor plate shall be per manufacturer's recommendation, but in no case shall it be less than 1/4" in thickness.

Thanks

Jeff Cook

Purchasing Agent

City of Cottonwood